MARYLAND HISTORICAL TRUST DETERMINATION OF ELIGIBILITY FORM

NR Eligible: yes _____

operty Name: Horsmon Tobacco Barn D	Inventory Number: CT-1068
Address: 1805 Parran Road	Historic district: yes X no
City: St. Leonard Zip Code: 20685	County: Calvert
USGS Quadrangle(s): Broomes Island	
Property Owner: HORSMON, RICHARD A & PHYLLIS J Ta	x Account ID Number: 157655
Tax Map Parcel Number(s): 206 Tax Map Number	:34
Project: Dominion's Cove Point Expansion Project Agency:	FERC
Agency Prepared By: GAI Consultants, Inc.	
Preparer's Name: Matthew G. Hyland	Date Prepared: 11/22/2005
Documentation is presented in: MIHP form	
Preparer's Eligibility Recommendation: Eligibility recommended	X Eligibility not recommended
Criteria: X A X B X C X D Considerations: A B	CDEFG
Complete if the property is a contributing or non-contributing resource t	o a NR district/property:
Name of the District/Property:	
Inventory Number:yes	Listed: yes
te visit by MHT Staff yesX no Name:	Date:
Description of Property and Justification: (Please attach map and photo)	
Four tobacco barns, a modern pole barn, and two modern residences constitute the at Property. Tobacco Barns A and B (CT-1065 and CT-1066) occur approximately 250 this Section 106 architectural survey. The modern dwellings and outbuilding do not a	feet outside of the area of potential effect for
Barn D stands adjacent to an existing earth and gravel driveway that proceeds from the fields and adjacent to a natural gas transmission pipeline. The barn is a wood frame by foundations. The siding material consists of vertical wood boards. The barn has correct contains approximately eight scaffolds each. A shed roof extension has been appended	ouilding constructed on poured concrete pier agated metal roof coverings. The tobacco barn
Formerly used for the curing and processing of tobacco, the barn dates from circa 19 outbuildings found in the region. The property surrounding the barn no longer support development, with its associated undistinguished domestic architecture, occurs in the contribute to a potential rural historic landscape. The barn retains integrity of design, integrity of setting and association has been compromised by modern housing development.	rts tobacco production. Modern suburban vicinity of the resource. The barn does not materials, workmanship, and feeling, but its
MARYLAND HISTORICAL TRUST REVIEW	
Eligibility recommended Eligibility not recommended	
Criteria: A B C D Considerations: A	BCDEFG
MHT Comments:	
Andrew Cerri	6/12/06
Reviewer, Office of Preservation Services	Date
<i>NA</i>	
Reviewer, National Register Program	Date

200601758

NR-ELIGIBILITY REVIEW FORM


CT-1068

Horsmon Tobacco Barn D

Page 2

The barn does not embody distinctive characteristics of a type, period, or method of construction. It does not possess distinctive architectural values. It is not located in any known historic district. The potential to obtain information important in prehisotry or history from the barn does not exist. The barn is not NRHP-eligible under Criterion D. It is recommended as not eligible for listing under NRHP Criteria A, B, C, or D. Furthermore, this resource does not possess a significant relation to major historical trends at the national, state, or local level. It is recommended as not eligible for listing in the NRHP or the MRHP.

MARYLA	ND HISTO	RICAL	TRUST	REVI	EW							
Eligibility	recommend	ed		Eliş	gibility not recomme	ended						
Criteria:	A _ nments:	_B _	_c _	D	Considerations:	A	В	c	D	E	F	G
	Reviewe	r, Office	of Pres	ervatio	n Services	-		Date			-	
***************************************	Review	er, Nati	ional Re	gister I	Program			Date				





Horsman Barn D CT-1068 wall ville vicinity Calvert County matthew G. Holasel GAI consultants / Inc. Sidned Wielevatins, tacing Vit. MESONO. 2 MESO BOXX N N N-1-182 The Horsmon farm is located off Parran Road in St. Leonard. Access to the farm is private. The farm no longer produces tobacco and instead focuses on a variety of market crops (eg. hay, cantaloupes, pumpkins, and chrysanthemums). Horsmon Barn 'D' is located south and slightly west of the 19th century farmhouse. Oriented on a north-south axis, this barn forms a small courtyard with Horsmon Barn 'C'. The barn consists of several different components, including a 17 x 24 foot main block, a 17 x 17 foot extension to the north, a 16 foot wide extension to the west and a 10 foot wide lean-to machine shed. The barn has undergone a number of modifications and door relocations. The barn is enclosed with vertical planks and a corrugated metal roof. Constructions materials suggest a late 19th century date of construction for the original section and a 20th century date for the additions and extensions.

Survey No.

CT-1068

Magi No.

Maryland Historical Trust State Historic Sites Inventory Form

DOE __yes __no

1. Nam	e (indicate pr	eferred name)		
historic				
and/or common	Horsmon Barn D			
2. Loca	ation			
street & number	Intersection of	Mackall and Par	ran Rds	not for publication
city, town S	t. Leonard	vicinity of	congressional district	
state MD		county	Calvert	
3. Clas	sification	7		
Category district × building(s) structure site object	Ownershippublicboth Public Acquisitionin processbeing considerednot_applicable	Status occupiedX unoccupied work in progress Accessible yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation X other: UNUSed
4. Own	er of Prope	rty (give names ar	d mailing addresses	s of <u>all</u> owners)
name Mr. R	ichard and Mrs.	Phyllis Horsmon		
street & number	Mackall and Par	rand Roads	telephone no	586-0936
city, town St.	Leonard	state	and zip code MD	
5. Loca	ation of Leg	al Description	n	
courthouse, regi	stry of deeds, etcalver	t County Courtho	ıse	liber ABE 263
street & number		reet (MD 765)		folio 32
city, town	Prince Frederic	k	state	MD
6. Rep	resentation	in Existing	Historical Surve	eys
title			-	
			federal state	e county loca
date			The state of the s	
date	urvey records			

7	D		41.00
1.	ues	Crip	tion

Survey No. CT-1068

Condition
____ excellent
____ good

____ fair

___ deteriorated

unexposed

Check one unaltered Check one

X original site

__ moved

date of move

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

See Attachment.

8. Significance CT-1068 Areas of Significance—Check and justify below prehistoric ___ archeology-prehistoric ___ community planning landscape architecture ____ religion 1400-1499 _ archeology-historic _ conservation law __ science 1500-1599 × agriculture economics literature sculpture 1600-1699 _X architecture education military social/ 1700-1799 _ art engineering music humanitarian _X_ 1800-1899 _ commerce exploration/settlement philosophy theater _x_ 1900-_ communications transportation industry politics/government _ invention ___ other (specify) Specific dates **Builder/Architect** B C D check: Applicable Criteria: A and/or Applicable Exception: A B C D E F G Level of Significance: national state local

Survey No.

Prepare both a summary paragraph of significance and a general statement of history and support.

See Attachment.

iv. Ge	ographical Da	ata	
	nated property ne Broomes Island, MD do NOT complete UTM	references	Quadrangle scale 1:24000
Zone Eastin		⊥ B L J L	asting Northing
C		P	
Verbal bounda	ry description and justific	ation	
	and counties for propertie	s overlapping state or cour	nty boundaries code
state		county	© 1
state	code	county county	code
state 11. For name/title Tora	code code m Prepared I	county county	code
state 11. For name/title Tora Calvert Co	code code m Prepared I	county county gry trict Commission	code code
state 11. For name/title Tora Calvert Co	code rm Prepared I a L. Williamsen-Be bunty Historic Dis	county county g county g rry trict Commission nd Zoning date	code code

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

DESCRIPTION CT-1068

The Horsmon farm is situated at the intersection of Mackall and Parran roads. There are four barns on the farm. Horsmon barn D is slightly to the northeast of Horsmon barn C. Barn D is oriented on a north-south axis. Barns C and D are near each other, approximately one-quarter of a mile to the southwest from A and B. All four barns and the farmhouse are connected by farm roads. The old farm house sits on a hill to the west of A and B and to the north of C and D. Horsmon barn D is a complex structure formed of an original nineteenth century barn with two added sheds and an to the barn itself. The plan of this original small barn was cross-axial The early barn is built of hewn timbers and fully mature machine cut nails. Later additions are built of circular sawn lumber and wire nails.

The original twenty-four by seventeen foot barn is divided into eight foot bays. This original barn had a double door on the east side with a gambrel-shaped portico above. This door has been removed. There was also a four-foot wide door on the south side. In addition, there is an early pintel in place in the northwest corner post of the old section, where a door once stood. The sixteen by seventeen foot addition to the north has a nine foot wide double doorway on its north side. The overall barn now measures forty by seventeen feet. The original transverse plan has been converted to an aisle plan. The barn has two sheds, one to the east, and another to the west.

The original main barn is supported on wood and concrete blocks. These blocks support a frame of both hewn and circular sawn timbers with cut and wire nails. The posts are peeled logs joined via mortise and tenon joints with trunnels and the nailers are hewn and pit sawn with cut nails in place. The east wall also has studs at the intermediate four foot locations between the eight foot bays. The down braces are circular sawn with wire The early timbers occur primarily, though not exclusively, on the east side, whereas the west side has more recent materials (circular sawn and wire nails). This barn may have been built during a transitional period, or it may be that the west end has been largely rebuilt. The early barn is covered with vertical siding and there are some three plank wide sidehinged ventilation doors. There is evidence that the original north, east, and west sides of this early barn were sided. rafters of this early barn are on two foot centers and rest on a flat false plate. There are windbraces on each diagonal and two collars to support the roof. This roof is covered with sawn boards covered with tar paper. The barn was once used to hang tobacco, as evidenced by the tier pole supports separated by thirty-eight inches vertical distance. No poles run down the central axis, as the narrow width of the barn makes this unnecessary.

7. DESCRIPTION (CONT.) CT-1068

The addition measures sixteen by seventeen feet. It has a large double doorway on the north side. This doorway was widened. originally measured only five feet wide. The materials in this addition are circular sawn with wire nails. The peeled log posts rest on a concrete block support system, and the down braces are circular sawn joined via mortise and tenon and nailed with wire There are no visible shingle nailers or boards, and the roof is covered with corrugated metal. The rafters are on four foot centers and rest on a flat false plate. The roof is supported by two collars. The tier pole supports are separated by thirty-eight inches vertical distance. The siding on this addition is of tightly fit vertical boards with some three plank wide ventilation doors.

The barn is now used for hay storage. It is floored and has had all the tier poles removed.

The sixteen foot wide shed to the west is divided into eight foot bays. It has a sixteen-foot wide double doorway on its north side. The posts are earth-fast peeled logs. All other timbers are circular sawn with wire nails. All of the tier poles have been removed. It is covered with vertical siding, and randomly spaced hinged ventilation doors. The roof is a lean-to construction built on to the entire length of the barn. It is covered with standing seam metal, and its rafters are on four foot centers.

The shed to the east is slightly offset from the original barn towards the south. It measures ten feet wide and is a lean-to machine/equipment shed. There is no evidence of tobacco ever having been hung here. The posts are earth-fast peeled logs. All the other timbers are circular sawn and have visible wire nails. The corrugated metal roof is original.

8. SIGNIFICANCE CT-1068

Horsmon barn D is architecturally significant for several The plan and measurements of the original barn were somewhat unusual. The barn was extremely narrow and small. may not have been originally designed as a tobacco barn, although it was once used for this purpose. The materials and techniques used in the construction of the barn are also unusual. offset doors and eight-foot bays interrupted by studs. materials of the original barn combined circular sawn lumber, hewn lumber and cut and wire nails. As such, this barn may be transitional or just largely rebuilt. The board roof covered with tar paper has not been found in many barns. The eastern door of this original barn was unusual. The gambrel-shaped polygonal door frame remains, although the door has been removed. The addition built to the north is indicative of the twentiethcentury expansion of the tobacco industry. Also indicative of this expansion is the south shed, built sometime during the midlate twentieth century when large double doors accessible by vehicles became common. The east shed was also built during this period to serve for vehicle storage. The sequence of development and construction materials and techniques may help to date other barns in the future.

This barn also yields information regarding agricultural history in Southern Maryland. In February 1990, a tobacco barn survey was initiated in order to study the tobacco barns of Calvert County. Until fairly recently, tobacco was the most important farm crop of the county. More acreage was devoted to its cultivation than for both of the next most extensive farm products (corn and wheat). The barns and stripping houses related to this "Tobacco Culture" are widely recognized as the most common element on the rural landscape. These structures are also the most threatened, as the market for tobacco declines. They seem to have, at present, only limited capabilities for reuse. Many barns and stripping houses now stand empty. The purpose of this survey has been to gather information and document a wide sample of these structures before they disappear from the landscape.

Historic Period theme(s): ca. 1890-; Tobacco; Agriculture Geographic Organization: Western Shore Chesapeake Bay Calvert Cty MD Chronological/Developmental Period: 1890-Present


Resource Type(s): Tobacco Barn


The changes this barn has undergone are many. The north wall of the original barn, and its east and north doors have been removed. An addition was built to the north. The east shed and the west shed were also built at later dates probably sometime during the mid twentieth century. The original barn had a cross-axial plan, but as the barn now stands, it is a somewhat

8. SIGNIFICANCE CT-1068 (CONT.)

irregular aisle plan. The barn has been greatly expanded. It has also been converted for hay storage by the removal of the tier poles and the flooring of the barn. It is no longer used for tobacco and is solely used for hay and equipment storage.

CT-1068 BARN 2041 4/4/80 HORSMON BARNEY NE 5 = orig , element now removed Gambre Door 1 3×4500 U3 x4 Sew 3x4 Soud PINTEL + DROPSLOT FOR EARLY DOOR SHED 1





CT-1068 Horsmon Barn D' St. Leonard Tova L. Williamsen West March, 1990